Campsie Playing Fields

Omagh, Northern Ireland



Title of Contract	Campsie Playing Fields, Omagh
CRL Contract Number	012685
Contract Value	£230,000.00
Client	Education Authority Northern Ireland, Infrastructure & Capital Development, 1 Hospital road, Omagh, BT79 0AW
Where the works were carried out	Campsie Playing Fields, Crevenagh Road, Omagh, BT79 0EQ
Start Date	05/03/2018
Completion Date	08/11/2019
Main Stadium Contractors	Woodvale Construction, 59 Crevenagh Road, Omagh, BT79 0EX
Pitch Design	Clive Richardson Limited, 54 Derrycoose Road, Portadown, BT62 1LY

Clive Richardson Limited were engaged as a specialist sportsground contractor by Education Authority NI and Woodvale Construction to reconstruct four pitches and a synthetic cricket wicket at Campsie Playing Fields in Omagh.

Works involved the installation of new drainage system across the site to allow the the construction of four sand-carpet natural grass pitches. The soil profile was graded, stone picked and levelled before a layer of sand was added. Pitches

were then sown out and appropriate fertiliser applied. Rugby sockets and posts were installed on all of the pitches. A synthetic cricket wicket was also installed between two of the pitches. Pitches were marked out and an athletics tracked marked out around the perimeter. Long Jump and triple jump pits were also reconstituted with specialised Wexford sand.

The facilities are now used by a number of schools in the area on a daily basis.





Post Contract

Following the Completion of this contract, Clive Richardson Limited have worked closely with Education authority NI and Woodvale construction to delivery numerous similar school pitch projects across Northern Ireland.

More Information

For more information on this project please contact Priscilla McFarland, General Manager/Director, Clive Richardson Limited via post to 54 Derrycoose Road, Portadown, Co. Armagh, BT62 1LY; via email to pmcf@cliverichardsonltd.co.uk or via telephone on +44 (0) 2838852888