IRFU Aviva Stadium 3G Pitch

Dublin, Ireland



Title of Contract	IRFU Aviva Stadium Synthetic Pitch Replacement
CRL Contract Number	012700
Contract Value	€342,000.00
Client	Irish Rugby Football Union, 10-12 Landsdowne Road, Ballsbridge, Dublin 4, Ireland
Where the works were carried out	The Back Pitch, Aviva Stadium, Landsdowne Road, Ballsbridge, Dublin 4, Ireland
Start Date	02/07/2018
Completion Date	24/08/2018
Pitch Design	Stephen McNally, Clive Richardson Limited, 54 Derrycoose Road, Portadown, Co. Armagh BT62 1LY

The Irish Rugby Football Union appointed Clive Richardson Limited to carry out the replacement of the existing 3G pitch surface on ‘The Back Pitch’ adjacent to the Aviva Stadium in Dublin. The pitch is home to both Lansdowne Rugby Club and Wanderers Rugby Football Club.

Works included the removal of the existing synthetic pitch carpet and its infill materials. The e existing shockpad was set

aside for reuse. Repairs to and the regrading of the existing base were then carried out. The existing shockpad was re-installed with extra pieces added to replace damaged or defective areas. A new synthetic carpet was then supplied and installed on top of the shockpad and infilled per manufacturer's instructions.

Following the installation an independent test was carried out on the completed pitch surface to World Rugby 2016 standards.







Post Contract

Clive Richardson Limited continue to work closely with the IRFU to maintain and develop their portfolio of pitches across the island.

More Information

For more information on this project please contact Priscilla McFarland, General Manager/Director, Clive Richardson Limited via post to 54 Derrycoose Road, Portadown, Co. Armagh, BT62 1LY; via email to pmcf@cliverichardsonltd.co.uk or via telephone on +44 (0) 2838852888